

KERALA STATE SCIENCE AND TECHNOLOGY MUSEUM AND

PRIYADARSINI PLANETARIUM

VIKASBHAVAN .P.O. THIRUVANANTHAPURAM - 695 033
PHONE: 2306024, 2306025 (Planetarium Counter) FAX: 0471-446976

(A Govt. of Kerala Undertaking)

Quotation No - KSSTM/21/2025-CA

13-01-2026

QUOTATION NOTICE

Sealed quotations are invited for **Supply, Installation, Testing and Commissioning of Three Phase Electrical Wiring at Innovation Hub, RSC, Chalakudy** as specified in the schedule attached below/overleaf. The necessary superscription, due date for the receipt of quotations, the date up to which the rates will have to remain firm for acceptance and the name and address of officer to whom the quotation is to be sent are noted below. Any quotation received after the time fixed on the due date is liable to be rejected. The maximum period required for the completion of work should also be mentioned. Quotations not stipulating period of firmness and with price variation clause and/or 'subject to prior sale' condition are liable to be rejected.

The acceptance of the quotations will be subject to the following conditions:-

1. Withdrawal from the quotation after it is accepted or failure to supply within a specified time or according to specifications will entail cancellation of the order and purchases being made at the officer expenses from elsewhere, any loss incurred thereby being payable by the defaulting party. In such an event the Government reserve also the right to remove the defaulter's name from the list of the Government suppliers permanently or for a specified number of years.
2. No representation for enhancement of price once accepted will be considered during the currency of the contract.
3. Any attempt on the part of quotationers or their agents to influence the officers concerned in their favor by personal canvassing will disqualify the quotationers.
4. Special conditions, if any, printed on the quotation sheets of the quotationer or attached with the quotation will not be applicable to the contract unless they are expressly accepted in writing by the purchaser.

Superscription: Quotation No: KSSTM/21/2025-CA

Due date and time for receipt of quotations: **17/01/2026 3PM**

Date and time for opening of quotations: **17/01/2026 4PM**

Date up to which the rates are to remain firm for acceptance: - 60 days

Designation and address of officer to whom the quotation is to be addressed: Director,
Kerala State Science and Technology Museum, Vikasbhavan PO, Thiruvananthapuram.

695033.

Specification of the items are given in the annexure to this notice.

**Supply, Installation, Testing and Commissioning of Three Phase Electrical Wiring at
Innovation Hub, RSC, Chalakudy**

Sl no	Items	Qty	Amount
1	25mm ² x 4C Al. Armoured Cable	85 M	
2	10 SWG Bare Copper	170 M	
3	VDB 63 A 6way, D.D. DB	1 no	
4	L& T. FN 63 A TPN SFU with Enclosure	1 no.	
5	TPMCB (for VDB)	2 nos.	
6	SPMCB – C Curve (for VDB and Industrial Socket)	4 Nos.	
7	16 mm ² cu. Insulated PVC cable (FRLS) (Approx. 5 m from SFU)	20M	
8	25mm Conduit (M) ISI	15 M	
9	32mm Conduit (M) ISI	3 M + 8 M	
10	32mm Cable gland	2 nos	
11	32 mm cable gland earth clip	2 nos	
12	16 mm ² Ring lug copper (SFU side)	4 nos	
13	25 mm ² Ring lug Al.	8 nos.	
14	16 mm ² Banna lug Copper VDB)	4 nos	
15	10 mm ² Ring lug (Bart copper)	8 nos.	
16	4 mm ² Ring lug (Gland earthing)	4 nos	
17	Earth bur. (25 x 3 mm) (Tinned.)	2 nos.	
18	32 mm saddle clip (heavy)	250 nos.	
19	Fischer, screw, clamp etc, miscellaneous	LS	
20	6 mm ² cu. PvC insulated cable (VDB to Machine)	32 M	
21	M.C Industrial socket with MCB (for 3 ø supply)	2 Nos.	
22	MC Industrial Socket with MCB (for 1 ø supply)	1 no.	
23	4M PVC Open Box	3 nos	
24	4M Plate	3 nos	
25	16A Switch (Modular)	3nos.	
26	16 A Socket (Modular)	3 nos.	
27	Switch dummy	3 nos	
28	4 sq.mm FRLS PVC insulated cable	45M	
29	63 A 4 P Isolater (For VDB as Incomer) , Lathe, Milling Machine Industrial socket)	3 nos.	
30	Labour charge		
	TOTAL		

Specification

1. Contractor should visit the site to assess the current conditions before submitting the bid
2. Total cost includes labour, materials, scaffolding, loading, transportation, unloading and other related expenses
3. The work has to be completed depends on site conditions

4. Entire works have to be carried out as per the direction of officer in charge
5. The rate quoted shall be inclusive of all taxes.
6. Works should be completed within 5 days from the date of Work Order being issued.

P88U
13/1/26
for DIRECTOR